

NHERI TALLWOOD PROJECT Updates 2020


NHERI TallWood Team

Discussion Topics

- Brief Overview / Recap on Project objective/vision
- What have been done?
 - Archetype development
 - Two-story test (shake table)
 - Assembly level test (biaxial cyclic)
- What is on-going?
 - Numerical modeling
 - Non-structural system inclusion
 - Resilience-based seismic design
- Updates on 10-story Shake Table Test
 - UCSD Table upgrade timeline
 - Design and Development
 - Construction planning
 - Steps forward with tentative schedule









What's Done? Two-story Test

- We completed a 2-story building test with PT CLT rocking walls in 2017.
- All results and publications now available on Project Website
- Main take-away:
 - The structural system can be damage free at all DBE and some MCE shakes
 - Numerical model works
 - Prototype connections and detailing work
 - Collaboration is key to get this done





Two-story building tested during Summer of 2017








Phase	Objective	Schedule
Phase II.1-S	 Investigation of the behavior of repaired SC-CLT wall (configuration [1]) under bidirectional loading (repaired foundation) Investigation of the deformation behavior of the gravity connection under reduced-scale gravity load Investigation of the deformation behavior of the gravity connection when the rotation of the steel seat is restrained 	Last week o March
Phase II.2-S	Investigation of the behavior of repaired SC-CLT wall (configuration [2]) under bidirectional loading	
Phase III	Investigation of the response of the SC-CLT wall (new wall) and a new connection (if needed) under predefined bidirectional earthquakes displacement time histories	
































Extension to Exterior Walls/Building Skins

- Many detailing issues for interior walls are relevant to exterior walls, but with the addition of windows/glazing.
- Racking tests validate the drift compatible performance of curtain walls, window walls, but extensive glass damage is typical, even in moderate shaking.

Systems of Interest	Class of Variation	Variations Considered
Storefront	Glazing method	Mechanically captured vs structurally glazed
Curtain wall w/ glazing	Glass aspect ratio	Varied from 1:2 to 2:1
Stick built curtain wall	Glass treatment	Heat strengthened vs. fully tempered
Unitized curtain wall	Glass type	Laminated and insulating glass units (IGU)
Light-framed with windows	Framing style	Balloon vs platform framed
Light gage steel stud framing	Finish material	Metal panel, wood shingle, and stucco
Wood stud framing	Window type	Fixed or operable, variable size
	Window framing	Metal or wood framed
	Glass variations	Same variables as for curtain walls may be applied

Partnership with Construction Specialties to Explore Stair Detailing

- CS DriftReady[™] Stairs detailed with slip joint to accommodate interstory movement
- Details to be explored
 - Incorporation into scissor stairs with intermediate landing
 - Connection to the main structural system
 - Interaction with surrounding fire protection walls



What's On-going? RBSD

- Resilience Based Seismic Design Task
 - Developing a quantitative approach to design tall wood buildings to hit a predefined resilience (i.e. down time) level after an earthquake.
- Led by Colorado State University Team




Co-PI: John van de Lindt jwv@engr.colostate.edu



Ph.D. student: Jace Furley

Objectives


- NIST Hazard Levels Linked With Proposed Performance
 - Routine: 50 to 100 year MRI, 64%-39% PO.
 - No Damage (Immediate Full-Recovery)
 - Design: 500 year MRI, 10% PO.
 - Immediate Functional Recovery (REDi Repair Class = 1 or lower)
 - Extreme: 2,500 year MRI, 2% PO.
 - Immediate Re-Occupancy (REDi Repair Class = 2 or lower)





Objectives (cont.) · Proposed Design Performance Objectives Routine: 50% NE Probability Structural: Repair Repair Description • ISD < 1.6% (UFP Yielding) Class Heavily damaged structural or non-structural components which pose risk to 'lfe-safety' and must be repaired to achieve Re-occupancy. Consequently, these components must also be repaired to achieve Functional Recovery and Full Recovery, since by definition they follow · Non-Structural: • Floor Acceleration < 0.72 g (HVAC Chiller) • ISD < 0.4% (Interior Partition Walls) Functional Recovery, and run Recovery, since by demandin they todow Re-occupancy. Damaged non-structural components which do not pose a 'life-safety' risk or otherwise hinder Re-occupancy but must be repaired to achieve Functional Recovery. Consequently, the component must all be repaired to achieve Full Recovery, since by definition it follows Functional · Design: 50% NE Probability Structural: 2 • ISD < 1.6% (UFP Yielding) Recovery. Minimal or minor cosmetic damage to *structural or non-structural* mponents which do not hindler Re-occupancy or Functional Recovery bu must be repaired to achieve **Full Recovery**. · Non-Structural: • Floor Acceleration < 0.72 g (HVAC Chiller) • ISD < 1.9% (Interior Partition Walls) • Extreme: ISD < 1.6% 50% NE Table 2: REDi Repair Classes · Structural: ISD < 1.6% (UFP Yielding) · Non-Structural: • Floor Acceleration < 1.5 g (HVAC Ducts) • ISD < 1.9% (Interior Partition Walls)

Objectives (cont.)


- Proposed Time to Functionality Objectives
 - Routine: 0 weeks to Full Recovery
 - Design: 0 weeks to Functional Recovery (Repair Class 1 or lower)
 6 weeks to Full Recovery
 - Extreme: 0 weeks to Re-Occupancy (Repair Class 2 or lower)
 - 12 weeks to Functional Recovery
 - 14 weeks to Full Recovery













Updates on 10-story tallwood test


- UCSD Shake Table upgrade
 - The table will have 3D capacity for our test
 - It is ongoing, so far on schedule (complete by 2/2021)
 - One quick testbed structure test (1 month) will be conducted on the table before we get on (Good for us)
- Preliminary design of the building is complete
 - Gravity frame design done, connection details TBD
 - Lateral design done (CLT rocking wall), initial simulation done, RBSD to follow, MPP rocking wall design to follow
 - Waiting for Wood Innovation Grant results (05/2020) for inclusion of NLT/DLT floors





Gravity Design Summary

- Gravity Design following NDS
 - Total floor dead load = 70 lb/sq.ft. (3.35kN/m2)
 - Total floor live load = 65 lb/sq.ft. (3.1 kN/m2)
- Final size of the members
 - Columns (12.25 x 12 ~ 15 in) (31 x 30 ~ 38 cm)
 - Beams (12.25 x 13.5 in) (31 x 34 cm)
 - CLT floor (5-ply CLT, 6 in) (15 cm)
 - Rocking wall panel (9-ply CLT, 12 in) (30 cm)
 - All sizes considering 2-hr fire sacrificial layers (3.6 in) (9 cm)



Tentative Schedule-10st Test

- 05/2020: Contractor selected and engage in design (Currently working with Swinerton and a few others to obtain quotes)
- 07/2020: Design and Detailing complete
- 09/2020: Final Construction package complete
- 10/2020: All material production orders in place
- 03/2021: First batch of construction material arrive @ UCSD
- 04/2021: UCSD shake table upgrade complete, ready for construction
- 05~08/2021: Construction + Instrumentation
- 09/2021~02/2022: Building Testing (may contain different phases)
- 03/2022: Disassemble of the building specimen

Consider joining the team if interested.

Project Information

www.nheritallwood.mines.edu

Information on this project and past results


- List of published papers
- Some presentations

10-story building:

- Revit model of the current gravity design
- A summary of 10-story building structural frame sizes and configurations
- Important updates

Contact me if there is any questions: spei@mines.edu

Questions and Open Discussion



Seriously, Folks: Questions & Comments